



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको  
कोटेशन माग गरिएको सुचना  
(सुचना प्रकाशित मिति २०८१/०५/११)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance and Modification at Centre Lab** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०७९/०८० को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ३ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा [quotation.procurement@bpkihs.edu](mailto:quotation.procurement@bpkihs.edu) मा email मार्फत पेश गर्नुपर्नेछ । BOQ को कागजात यसै साथ संलग्न गरिएको व्यहोरा अनुरोध छ ।

# B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

## COST OF ESTIMATE

NAME OF PROJECT:- Renovation work.

PLACE: Central lab ,ward sample collection area.( lab room no 13-16 )

S. N.	Work Description	Unit	Quantity	Rate In Number	Rate In Words	Total
1	Dismantling of brick masonry wall.	cft	291.70			
2	p/laying first class chimney made brick work in@1:4 c/m.	cft	22.19			
3	p/laying of glazed ceramic wall tile approved brand20mm thick under bedded mortar in@1:4 with joint filling etc all complete work.	sft	165.10			
4	p/laying of non-skid floor tile approved brand20mm thick under bedded mortar in@1:4 with joint filling etc all complete work.	sft	54.49			
5	P/fitting of UPVC door 100*60mm white color with top and bottom UPVC panel with 10" sliding handle ,8" cheskiney ,6"handle, 5' hinge ,nails ,screw etc all complete work .	sft	42.00			
6	p/applying two or more coat of distemper paint .	sft	2,425.67			
7	p/fitting aluminium frame fixed partition without door alu.natural anodized 63*38*1.3mm with 5mm clear glass or acp board including screw ,rubbar gasket ,clip etc all complete.	sft	189.01			
8	p/fitting aluminium frame one way openable casement door with alu.natural anodized 63*38*1.3mm with 5mm clear glass or acp board including screw ,rubber gasket ,andnecessary new hard ware fitting etc all complete.	sft	37.32			

9	Demolition of RCC or RBC with 10 M. lead etc. all complete.	cft	19.09			
10	Removal of door shutter with choukhats.	no	1.00			
11	Fitting of door shutter with choukhat with existing hardware with new hold fast and screws.	no	1.00			
12	P/laying of 12.5MM thick cement plaster in @1:4 c/sand mortar etc. all complete.	sft	45.67			
13	metal frame with round bar mesh fencing work- P/ fabrication and installation of 38mmx38mmx5 mm or equivalent size frame with 20mmx5mm m.s plate WITH 6 MM OR EQUIVALENT SIZE BAR MESH FANCING @3.5"X3.5" SPACING OPENINGS including aluminum paint two coats with metal primer complete work ready for used as per design , drawing and instruction.	kg	378.00			
14	P/fitting of 110 MM dia PVC floor trap etc. all complete.	set	4.00			
15	P/laying of 110 MM dia PVC pipe 6K.G./CM square presure etc. all complete.	rft	20.00			
16	P/fitting of 110 MM dia PVC door bend etc. all complete.	no	2.00			
17	P/fitting of 110 MM dia PVC door tee etc. all complete.	no	1.00			
18	P/laying of 50 MM dia PVC pipe 6K.G./CM square presure etc. all complete.	rft	20.00			
19	p/fitting 50mm dia pvc elbow.	no	3.00			
20	P/fitting of 50 MM dia PVC door tee etc. all complete.	no	2.00			
21	P/fitting of 15 MM dia G. M. gate valve etc. all complete.	no	1.00			
22	P/laying of 15 MM dia G. I. pipe medium class with fittings etc. all	rft	40.00			

	complete.					
23	p/fitting of 16"*22" size ceramic wash basin with angle cock,pilar cock ,conection pipe botal trap etc all complete work .	set	1.00			
24	other's : site clearance all dismantling rubbish material out side the camp area,etc as per instruction of site engineer.	L/S	1.00			
			Total:-			
			13% VAT			
			Grand Total:-			