

वी.पी.कोइराला स्वास्थ्य विज्ञान प्रतिष्ठान धरानको कोटेशन माग गरिएको सूचना । (पुन: सूचना प्रकाशित मिति:२०८१।०९।१७)

यस प्रतिष्ठान अन्तर्गत रहेको Guest House को मर्मत, संभार र पेन्टिङ्ग कार्य गर्नुपर्ने भएकोले संलग्न विवरण बमोजिमको कार्यको लागि व्यवसाय (फर्म) दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व. २०६०/०६१ को कर चुक्ताको प्रमाणपत्र प्रतिहरू संलग्न गरी यो सुचना प्रकाशित मितिले ५ (पाँच) दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोिकएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा खामबन्दी दर्ता गर्नुहुन वा $\frac{1}{2}$ \frac

Name of Project: painting and repair work.

Location: Guest house area.

SN	Work Description	Unit	Quantity
7	P/applying single coat of cement		
1	primerprimer.	Sft.	2094.817
2	P/applying single coat of wood primer.	Sft.	671.558
	P/applying two or more coat of distemper		- 0, 2,000
3	paint	Sft.	11953.708
	P/applying two or more coat of plastic		
4	emulsion paint	Sft.	43609.667
	P/applying two or more coat of enamel paint.		•
5		Sft.	10089.936
	P/applying three or more coat of chapra		
6	polish.	Sft.	2922.026
	P/applying two or more coat of weather proof		
	exterior emulsion weather coat paint.		
7		Sft.	14333.815
	P/applying two or more coat of aluminium	0	500 1000 1000 1000 1000 1000 1000 1000
8	panit.	Sft.	660.599
	P/applying two or more coat of black japan		
9	paint.	Sft.	626.245
	P/fitting of 19MM thick water proof plyboard		
	with required nails/screws and existing		
10	hardware should be fitting etc. all complete.	Sft.	32.272
	Removel of A.C. sheet made damaged roof		
11	with ridge etc. all complete.	Sft.	819.250
	P/laying of 0.42MM thick colour CGI sheet		
	with required hilty not/bolts etc. all complete.		
12		Sft.	819.250
	P/fitting of 26 guage colour plain sheet with		
13	hilty nut/bolt etc. all complete.	Sft.	266.236
	P/laying of 12.5MM thick cement plaster in		
14	@1:4 cement sand mortar etc. all complete.	Sft.	223.083
	P/laying of PCC in @M15 grade cement		
15	concrete etc. all complete.	Cft.	19.547
	Removel of dameged door shutter etc. all		
	complete.	Nos.	2.000

	P/fitting of 32MM thick water proff door shuter and aluminium sheet with 3 of of 5" size		
	kabja, 2 no of 6"alu Cheskini, 2 no of 6" alu.		
	Handle, 1 no of 10" L- drop with required		
17	nails/screws Etc all complete	5ft.	13.267
	P/fitting of 32MM thick water proff door shuter		
	with 3 of of 5" size kabja, 2 no of 6"alu.		
	Cheskini, 2 no of 6" alu. Handle, 1 no of 10" L-		1
	drop with required nails/screws. Etc all		*
18	complete.	Sft.	18 688
	Removel of dameged parquet etc all		
19	complete.	Sft.	1300.609
	P/ fitting of 150MM*30MM*8MM size teak		
20	wood floor parquet etc. all complete.	Sft.	1300.609
	P/ fitting of 12"size brass made lucking set		
21	etc. all complete.	Nos.	32.000
22	Providing of anti-termite chemical.	Lts.	6.000
	P/layinging of ordinnery form work with after		
	removel of complition woek etc. complete		
23	work.	Sft.	23.993
neres e	P/fitting of 15MM dia wall mixture with thread		
24	sill tape etc. complete	Nos,	10.000
	OTHERS - Old painting surface cleaning work, crack		
	filling by puttin or c/s mortar, primer touch-up, arrange		
- 1	scaffolding other related on sean work, rubbish	L/S	1.000
25	disposal site clearance	173	