



## बी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

### कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/०३/२३)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance of Boundary Fencing Wall at near hostel no 3** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा [quotation.procurement@bpkihs.edu](mailto:quotation.procurement@bpkihs.edu) मा email मार्फत पेश गर्नुपर्नेछ ।

**B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES****DHARAN****COST OF ESTIMATE**

Name of project : Repair of boundery  
fenceing wall.

Place :In hostel area in near in hostel No. -3.

<b>S. N.</b>	<b>Work Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate in Number</b>	<b>Rate in Words</b>	<b>Amount</b>	<b>Remarks</b>
1	Removal of brick masonry etc. all complete.	Cft.	237.81				
2	Removal of PCC etc. all complete.	Cft.	31.30				
3	Removal of metal and wire mesh fence bar with metal post etc. all complete.	Sft.	630.00				
4	E/work in excavation in gravel mixed soil with all-purpose excavation etc. all complete.	Cft.	127.50				
5	E/work in filling with 15CM layer by layer with compaction etc. all complete.	Cft.	127.50				
6	P/laying of first class chimney made brick work in @1:4 cement sand mortar etc. all complete.	Cft.	237.81				
7	P/laying of PCC in @M15 grade with crushed agg. Etc. all lead and lift etc. all complete.	Cft.	31.30				
8	P/laying of ordinary form work with after removal completion of work etc. all complete.	Sft.	157.61				
9	P/laying of ave. 12.5MM thick cement plaster in @1:4 cement sand mortar etc. all complete.	Sft.	340.00				
10	P/laying of 6MM thick pebbles with base of cement plaster in @1:4 cement sand mortar with required listy wood framing etc. all complete.	Sft.	325.81				
11	Installation of existing metal and wire mesh fence made boundary bar with normal repair with wíelding machine, wilding rod, welder and w/helper etc. all complete.	Sft.	383.82				
12	P/making and Installation of metallic frame for boundary bar with welding machine, wilding rod, welder and w/helper etc. all complete.(Beans like a bar)	KG.	194.61				
13	P/making and Installation of 75MM outer dia round black tube3.25MM thick etc. all complete.	KG.	91.65				

14	P/fitting of 2" opening 10SWG wire (Heavy coated) mesh fence in metallic frame etc. all complete.	Sft.	219.32				
15	P/applying single coat of metal primer .	Sft.	219.32				
16	P/applying two or more coat of enamel paint .	Sft.	548.31				
17	OTHERS : Rubbish material disposal, minor repair or rectification work, other related work, site clearance.	L. S.	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				