



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको
कोटेशन माग गरिएको सुचना
(सुचना प्रकाशित मिति २०८२/०५/१६)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance and Painting of A1 Building** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा quotation.procurement@bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

Name of project : Painting and
repair work.

Place : A1block.

SN	Work Description	Unit	Quantity	Rate in no	Rate in Words	Amount	Remarks
1	P/applying single coat of cement primer.	Sft.	240.33				
2	P/applying single coat of wood primer.	Sft.	91.85				
3	P/applying two or more coat of plastic emulsion paint.	Sft.	4,400.75				
4	P/applying two or more coat of enamel paint.	Sft.	2,153.32				
5	P/applying three or more coat of chapra polish.	Sft.	294.22				
6	P/applying two or more coat of weather proof exterior emulsion paint.	Sft.	1,746.55				
7	P/fitting of stainless steel mosquito net jalli with required screws etc. in metallic frame all complete.	Sft.	114.77				
8	P/fitting of stainless steel mosquito net jalli with diamond mesh required bead/nails screws etc.in wooden frame all complete.	Sft.	32.79				
9	P/fittig of 4MM thick clear plain glass with required putty /screws etc. all complete.	Sft.	8.26				
10	P/making and fitting of 19MM thick water proof plyboard with around 3/4"*1/2"size sesum bead with 2No. of 3" size kabja, 1No. of 4" size brass handle , 1No. of luck with required nails/screws etc. all complete.	Sft.	11.00				
11	P/making and fitting of sal wood choukhat frame with required hold fast or equivelent with required nails/screws etc. all complete.	Cft.	0.68				

12	P/fitting of 19MM thick water proof plyboard with required nalis etc. all complete.	Sft.	4.58				
13	P/laying of 12.5MM thick cement plaster in @1:4 cement sand mortar etc. all complete.	Sft.	78.66				
14	P/fitting of sun mica with required nalis and glue etc. all complete.	Sft.	8.00				
15	P/fitting of 4MM thick bathroom mirror with required screws/rawel plug/beads etc. all complete.	Sft.	12.00				
16	P/laying of water proofing chemical coating over well cleaned and brushed roofing surface with sealing of joints with crack seal securing for leakage control works as per instruction complete work.	Sft.	581.70				
17	P/laying of 50MM thick cement screeding work in @M15 grade cement concrete with punning etc. as per instruction complete work.	Sft.	581.70				
18	Supplying required related hardware goods with providing of man power.	P. S.	1.00				
19	OTHERS :- Old painting surface cleaning work, crack filling by puttin or c/s mortar, primer touch-up,damaged jalli and glass removal work, damaged plaster removal, hacking work in terrace for screeding work ,other related on sean work,rubbish disposal,site clearance.	L.S.	1.00				
IN WORDS:-			Total = Rs.				
			13% VAT Amount = Rs.				
			Grand Total = Rs.				