



## बी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

### कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/०६/१२)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance and Painting of Psychiatric Office, Bld no 111** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र (अन्तिम मिति: २०८२/०६/२४) कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा [quotation.procurement@bpkihs.edu](mailto:quotation.procurement@bpkihs.edu) मा email मार्फत पेश गर्नपर्नेछ ।

# B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

## COST OF ESTIMATE

NAME OF PROJECT:-Painting and Gypsum board false ceiling work etc.

PLACE: Psychiatry office building & Building no -111.

S. N.	Work Description	Unit	Quantity	Rate in no	Rate In Words	Amount	Remark
1	P/applying two or more coat of distemper paint Over a coat of cement primer.	sft	1,542.92				
2	P/applying two or more coat of Enamel paint .	sft	750.51				
3	P/fixing 12mm thick gypsum board false ceiling with all necessary Nails, screw etc as per design & instruction of site engineer.	sft	417.00				
4	p/applying two or more coat of weather proof or equivalent exterior emulsion paint over a coat of cement primer.	sft	2,772.40				
5	p/fitting 50*25mm size sal wood masqtonet jalli fram with stenless steel masqtonet jalli and 4mm thick com. Ply in back saport and saport gudka required nails, screw ,including two ormore coat of enamel paint over acoat of wood primer.	sft	121.49				
6	P/applying single coat of cement primer .	sft	209.67				
7	P/applying single coat of wood primer .	sft	540.84				
8	P/applying two or more coat of Aluminium paint .	sft	240.00				
9	P/laying 1st class chimney made brick work in @1:4 c/m.	cft	11.37				
10	P/laying 12.5mm thick cement sand plaster work in @1:4 c/m.	sft	496.39				

11	p/laying RCC/ pcc work in @1:1.5:3(M20 grade ) cement concrete with crushed aggregate etc all complete.	cft	52.13				
12	p/laying & placing reinforcement cutting bending binding etc all complete.	kg	168.95				
13	p/fitting ordinary form work shuttering centering with dismantling etc all complete.	sft	337.30				
14	other's : sidelining the old or rough surface to be painted area minor crack filling by putting, minor touch up, minor plaster, minor cement & wood primer work and existing damage false ceiling removal and floor dismantling etc other related work.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				