



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/०७/१७)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **(1) Repair and Painting Work at CLS (2) Repair and Painting Work at ECG and Serology (3) Repair and Maintenance of Aluminum door and Metal Door at Emergency area** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा quotation.procurement@bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES
DHARAN
COST OF ESTIMATE

NAME OF PROJECT:- Painting & maintenance work.

PLACE:CLS lab common area, sample collection room ,passage area etc

S. N.	Work Description	Unit	Quantity	Rate No	Rate in Words	Amount	Remark
1	p/applying two or more coat of distemper paint over a coat of cement primer.	Sft	4,520.17				
2	p/applying two or more coat of enamel paint over a coat of cement primer.	Sft	1,128.42				
3	p/applying two or more coat of Aluminium paint over a coat of metal primer.	Sft	73.70				
4	Dismantaling& re-fitting & fabrication and installation of collapsable gate maintenance with normal hard ware fittings etc as per instruction.	kg	196.25				
5	p/fabrication of 40*10mm flat strip iron and 40*40*5mm equal angle etc as per instruction of site engineer.	kg	16.45				
6	p/ fitting of 2" die metal wheel.	no	4.00				
7	other's: site clining the old or rough surface to be painted area miner crack filling, miner touch etc other releted work.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				

**B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES
DHARAN
COST OF ESTIMATE**

NAME OF PROJECT:- Painting work.

PLACE:ECG Room no -8 ,Serology room no-29

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	p/applying two or more coat of distemper paint over a coat of cement primer.	Sft	1,267.40				
2	other's: site clining the old or rough surface to be painted area miner crack filling, miner touch etc other releted work.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Channel gate Repair work

PLACE:Emergency area.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	P/fitting aluminum frame one way open able casement door with alu.natural anodized 101.6mm*45mm*1.5mm with 5mm clear glass or acp board including screw ,rubber gasket ,unnecessary new hard ware fitting etc all complete.	Sft	19.21				
2	Dismantaling& re-fitting & fabrication and installation of collapsable gate maintenance with normal hard ware fittings etc as per instruction.	Sft	218.54				
3	p/fabrication of 40*10mm flat strip iron and 40*40*5mm equal angle etc as per instruction of site engineer.	kg	16.45				
4	p/ fitting of 2" die metal wheel.	No	4.00				
5	P/fitting & fabrication and installation of collapsable gate 4"*4" opening with required no of repit,holdfast etc as per design & instruction of site engineer.	kg	155.56				
6	F/ fabrication and installation of 25 mmx25mmx2mm thick squire pipe Metal gate frame and 25 mmx25mmx2 mm thick squire pipe internal Vertical member with 3mm M.S plate and metal sliding handle, metal cheskinney 10",and metal hing ,etc as per design& instruction of site engineer.(gate size - 2'9"*6'8"=2.0no)	kg	104.48				
7	p/applying two or more coat of enamel paint over a coat of metal primer.	Sft	173.68				
8	other's: siteclirance all disposal rubbish material out side the camp area, existing floor cutting &minar floor pcc work,dismaintal collapsable gate dispose side to engineering work shop area 3no old existing grill cutting and welding&fabrication work etc others releted work.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				