



## वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

### कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/०७/१७)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **(1) Repair and Painting Work at Psychiatric Ward** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा [quotation.procurement@bpkihs.edu](mailto:quotation.procurement@bpkihs.edu) मा email मार्फत पेश गर्नुपर्नेछ ।

**B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES**

**DHARAN**

**COST OF ESTIMATE**

**NAME OF PROJECT:-** Mosquito net jalli replacement work and stor room renovation work .

**PLACE:**psychetric ward.

<b>S. N.</b>	<b>Work Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate in No</b>	<b>Rate in Words</b>	<b>Amount</b>	<b>Remark</b>
1	p/fitting stainless steel mosquito net jalli with back saport 4mm thick com. Ply wood and nails, screw and two or more coat enamel paint etc all complete work.	sft	319.88				
2	p/fitting stainless steel mosquito net jalli with daimond mess jalli and nails, screw etc all complete work.	sft	200.95				
3	p/fitting 50*25mm size Sal wood mosqutonet jalli fram with stainless steel masqutonet jalli and 4mm thick com. Ply in back saport and saport gudka required nails, screw ,including two ormore coat of enamel paint over acoat of wood primer.	sft	129.29				
4	F/fabrication and installation of 40MM*40MM*5MM size sport equaled angle with hole etc as per design and instruction of site engineer.	kg	131.04				
5	P/laying 12 SWG barbed wire (medium coated) with required binding wire.	rft	750.00				
6	P/laying first class chimney made brick work in@1:4 c/m.	cft	81.90				
7	p/laying 12.5mm thick cement sand plaster work in @1:4 c/m.	sft	440.32				
8	p/laying Rcc/ pcc work in@1:2:4 cement concrete with crushed aggregate etc all complete.	cft	6.73				
9	P/laying & placing reinforcement cutting bending binding etc all complete.	kg	30.49				
10	P/fitting ordinary form work staring with dismantling etc all complete.	sft	31.21				
11	P/fitting of 19 MM thick waterproof plywood with required nails/screw etc. all complete.	sft	90.00				
12	Dismantling of pcc of existing floor area.	cft	5.99				
13	Earth work excavation infoundation gravel mixed soil.	cft	6.00				
14	P/laying pccwork in@1:2:4 cement concrete with crushed aggregate etc all complete.	cft	9.00				
15	p/applying two or more coat of distemper paint over a coat of cement primer.	Sft	184.75				
16	p/applying two or more coat of exterior emulsion paint over a coat of cement primer.	Sft	255.57				
17	p/applying two or more coat of Enamel paint over a coat of wood primer.	Sft	180.00				
18	p/applying two or more coat of Enamel paint over a coat of metal primer.	Sft	116.60				

19	P/fitting of 32MM thick water proff door shuter with alu. sheet with 3 of 4" size kabja,2 on of 6"alu. chiskini, 2 no of 6"alu. Handle, 1 no of 8" L-drop required nails/screwsetc. all complete.	Sft	47.50				
20	p/fitting32 mm thick water proof false door shutter with back saport aluminium sheet and 6" inch length isi hing and 3no , 6"aluminium handle,8" aluminium cheskiney ,10" G.P sliding handle with nails screw etc all complate work.	Sft	95.00				
21	OTHERS :- Site clearance Rubbish disposal work other related work and existing gate dismantling & re- fitting work etc all complete.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				