



## बी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

### कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/०८/०१)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair and Maintenance at Different Area (allocated Futkar Works)** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा [quotation.procurement@bpkihs.edu](mailto:quotation.procurement@bpkihs.edu) मा email मार्फत पेश गर्नुपर्नेछ ।

**B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES  
DHARAN  
COST OF ESTIMATE**

NAME OF PROJECT:- Painting, Aluminium partition, wooden cabinet, ccgi sheet shed work.

PLACE: Serotve room, x-ray class room, Liquid oxygen plant, ortho observation, palmo icu, psychiatric faculty office.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
	(A)Dialysis unitserotve room/GOPD top room no-120						
1	p/applying two or more coat of Distemper paint over a coat of cement primer etc all complete.	sft	1,474.50				
2	Other's : Site cleaning the old or rough surface to be painted area minor crack filling, minor touch up etc other related work.	L/S	1.00				
	(B)x-ray class room and faculty room-						
3	p/applying two or more coat of distemper paint .	sft	1,456.83				
4	p/applying two or more coat of enamel paint .	sft	1,103.46				
5	p/applying single coat of cement primer paint .	sft	793.93				
6	p/applying two or more coat of Aluminium paint over a coat of metal primer .	sft	113.65				
7	other's :site cloning the old or rough surface to be painted area ,minor crack filling ,minor touch up, minor plaster work etc other related work.	L/S	1.00				
	(C)Liquid oxygen plant truss shed work.						
8	F/ fabrication and installation of 50*50*1.8 mm square pipe for sad vertical post and 40*40*1.2mm thick square pipe rafter and purling etc as per design and instruction of site engineer.	kg	220.25				
9	p/fitting of 0.42mm thick color CCGI sheet with hilt washer etc all complete.	sft	456.00				
10	Earth work excavation in foundation gravel mixed soil.	cft	30.38				
11	p/laying pcc work in @ 1:2:4 cement concrete with crushed aggregate etc all complete.	cft	30.38				
12	p/applying two or more coat of enamel paint over a coat of metal primer .	sft	140.14				

13	P/fitting of 3" opening 10 SWG wire fence heavy coating with binding wire and fitting of boarder (string) wire etc. all complete.	sft	580.00				
14	p/fitting & laying 10 SWG wire (medium coated) fore boarder wire with binding wire etc all complete .	rft	310.00				
15	F/ fabrication and installation of 25 mm dia 3.25mm thick M class black pipe compound gate frame with 20*20*3mm equile angle saport and 20*3mm flate strip saport and vala and 3mm M.S plate and metal sliding handle, metal cheskinney 10", and metal hing ,etc as per design& instruction of site ingineer.	sft	24.00				
16	other's : site clearance disposal all rubbish materials outside of institute area minor apron drain maintenance work etc all complete.	L/S	1.00				
	(D) Ortho obsurvation ward -						
17	P/fitting aluminum frame fixed partition without door alu.natural anodized 78*28*1.3mm with 5mm clear glass or acp board (Grew colour )or equavalent including screw ,rubbar gascate ,clip etc all complete	Sft	164.51				
18	p/fitting aluminium frame one way openable casment door with alu.natural anodized 78*28*1.3mm with 5mm clear glass or acp board including screw ,rubbar gascate ,andneccessary new hard ware fitting etc all complete.	Sft	37.32				
	(E)Pulmonary ICU Plywood cabinet for store room						
19	P/fabrication making and installation of plywood rack of various size at pulmonary ICU staircase area to manage as store area with following specifications and details as per instruction and satisfaction of site Engineer/design drawing.						
A.	cabinet size3'0"x6'0"x1'9" with 4 dividers horizontal 19mm ply with 2side and 6mm ply back covering from commercial plywood with wooden support beat and decorative wooden listy including chapra polish finishing complete with installation and transportation cost.	set	2.00				

B.	cabinet size 4'0"x5"x1'9" with 3 dividers horizontal 19mm ply with 2 side and 6mm ply back covering from commercial plywood with wooden support beat and decorative wooden listy including chapra polish finishing complete with installation and transportation cost.	set	2.00				
C.	cabinet size 5'0"x5'6"x1'9" with 3 dividers horizontal 19mm ply with 2 side and 6mm ply back covering from commercial plywood with wooden support beat and decorative wooden listy including chapra polish finishing complete with installation and transportation cost.	set	2.00				
D.	cabinet size 5'6"x5'6"x1'9" with 3 dividers horizontal 19mm ply with 2 side and 6mm ply back covering from commercial plywood with wooden support beat and decorative wooden listy including chapra polish finishing complete with installation and transportation cost.	set	1.00				
20	supply laying and fixing of wooden listy 20mmx12mm decoratives and nails over front beads as per instruction and design .	rft	227.50				
21	supply/ laying of bottom base support wooden gudka and levelling bitterns various size .	cft	3.48				
22	chapra police -p/applying of normal chapra police finishing overall size as per instruction.	sft	1,026.00				
23	other's :- site clearance all disposal rubbish materials out side the camp area ,provisiona for store room luck with metal pipe 50mmx50mmx8'0" and lucking arment and cabinet hanging work complete.	L/S	1.00				
(F) Psychiatric faculty office -							
24	P/applying two or more coat of distemper paint Over a coat of cement primer.	sft	1,542.92				
25	P/applying two or more coat of Enamel paint .	sft	442.76				
26	P/fixing 12mm thick gypsum board false ceiling with all necessary Nails, screw etc as per design & instruction of site engineer.	sft	417.00				

27	other's : sidelining the old or rough surface to be painted area miner crack filing by putting,minar touch up, miner plaster ,miner cement & wood primer work and existing damage false ceiling removal and floor dismantling etc other related work.	L/S	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				