



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको
कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/१०/१२)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance and Painting of F16.3.1 Building** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement@bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES
DHARAN
COST OF ESTIMATE

Name of project : Repair and painting work.

Place : F16.3.1.

SN	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remarks
1	Demolation or removal of damaged cement plaster.	Sft.	152.74				
2	Demolation or removal of damaged shutter of door.	No.	1.00				
3	Demolation or removal of damaged wash basin.	Set.	1.00				
4	P/applying single coat of metal primer.	Sft.	249.90				
5	P/applying single coat of wood primer.	Sft.	57.29				
6	P/applying two or more coat of plastic emulsion paint with one coat of cement primer.	Sft.	1,421.28				
7	P/applying two or more coat of enamel paint.	Sft.	906.67				
8	P/applying two or more coat of watherproof exterior emulsion paint with one coat of cement primer.	Sft.	53.59				
9	P/laying of 12.5MM thick cement plaster in @ 1:4 cement sand mortar.	Sft.	197.67				
10	P/laying of 1.5MM thick cement punnig etc. Aa comple.	Sft.	93.03				
11	P/laying of P/G/C wall tile with 20MM thick under beded cement plaster in @ 1:4 cement sand mortar.	Sft.	4.00				
12	P/laying of 4MM thick clear plain glass with required bead/gasket and nail/screws etc. all complete.	Sft.	31.77				
13	P/laying of stainless steel mosquito net jalli with required bead and nail/screws etc. all complete.	Sft.	107.93				
14	P/laying of stainless steel mosquito net jalli and diamond mesh with required bead and nail/screws etc. all complete.	Sft.	16.44				
15	P/fitting of 32MM thick water proof door shutter with one side aluminium sheet with 4"kabja-3Nos, 6"aluminium cheskini-2Nos.,6"aluminium handle-2Nos.,8"L-drop-1No. and required nail/screws etc. all complete.	Sft.	13.52				

16	P/fabrication and installation of metal square tube etc. all complete.	K. G.	28.29				
17	Fitting or fixing of metallic vantilation in window with welding machine,welder with welding rod and arrange scaffolding etc. all complete..	Job.	1.00				
18	P/fitting of plastic boarder type mirror etc. all complete.	No.	1.00				
19	P/fitting of 16"*22" size p/c/g wash basin with pedastal white glazed with bottle trap, PVC connection pipe , fancy pillar cock, C.P. angle cock , bracket , screws etc. all complete.	Set.	1.00				
20	P/fitting of p/c/g 20" size orissa pan with low level plastic flushing cystem , flush pipe, connnection pipe, angle cock etc. all complete.	Set.	1.00				
21	P/fitting of sal wood choukhat and required hold fast and nail/screws etc. all complete.	Cft.	0.48				
22	P/ making and installation of kit. Cupboard shutter with 19MM thick water proof ply board with 3/4"*1/2" size sesum bead around, 3nos of 3" size kabja, 1nos of k-nob, 1nos of m/luck with required nail/screws etc all complete.	Sft.	10.87				
23	P/laying of water proofing chemical coating over well cleaned and brushed roofing surface with sealing of joints with crack seal securing for leakage control works as per instruction complete work.	Sft.	511.26				
24	P/laying of 50MM thick cement screeding work in @M15 grade cement concrete with punning etc. as per instruction complete work.	Sft.	511.26				
25	Others : Old paninting surface cleaning work,crack filling by putting,damaged glass removal, damedged net removal,Damedged door frames part removal, damaged w/basin and d/shutter deposit in store or workshop,arrange scaffolding or lader other related on sean work,rubbish disposal,site clearance.	L. S.	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				