



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको
कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८२/११/०४)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Construction of Attached Toilet at Nursing College** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ। माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा quotation.procurement@bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

Name of Project : Attached toilet construction work .

Place : Chief room in nurshing collage in bldg No. -44.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remarks
1	Removel of hollow concrete block masonry as per instruction etc. all complete.	Cum.	17.74				
2	Removel of plain cement concrete as per instruction etc. all complete.	Cum.	3.62				
3	E/work in excavation in gravel mixed soil for all type excavation etc. all complete.	Cum.	397.69				
4	E/work in filling with 15CM layer by layer with compaction etc. all complete.	Cum.	337.50				
5	P/laying of frist class chimney dry flat brick solling with sand binding and cousion etc. all complete.	Sft.	24.08				
6	P/laying of PCC in @M10 grade cement concrete with crushed aggregate etc. all complete.	Cum.	5.04				
7	P/laying of PCC in @M15 grade cement concrete with crushed aggregate etc. all complete.	Cum.	31.11				
8	P/laying of 38MM thick cement screeding in @M15 grade cement concrete and punning with crushed aggregate etc. all complete.	Sft.	2.83				
9	P/laying of frist class chimney made brick work in @1:4 c/sand mortar etc. all complete.	Cum.	75.79				
10	P/laying of 12.5MM thick cement plaster in @1:4 c/sand mortar etc. all complete.	Sft.	232.22				

11	P/laying of PCC for RCC work in @M20 grade cement concrete with crushed aggregate etc. all complete.	Cum.	5.40				
12	P/cutting, bending, placing reber with binding wire etc. as per drawing, specification, instruction all complete.	K.G.	40.08				
13	P/laying of ordinary form work with nailing, supporting and after removal etc. all complete.	Sft.	28.75				
14	P/laying of 1.5MM thick cement punning etc. all complete.	Sft.	12.00				
15	ALUMINIUM SLIDING WINDOW : P/fabrication and installation of aluminium framed sliding window with Alluminium framed sliding window without ventilator and with mosquito net . (Alluminium - Natural anodised 101MM*38MM*1.3MM , glass - 5MM clear) 10.6MM series.	Sft.	4.00				
16	ALUMINIUM FRAMED CASEMENT WORK : P/ fabrication and installation of 101.60MM*45MM*1.5MM or equivelent or equivelent natural section aluminium framed casement door (One way openable) with 5MM thick clear glass with 9MM thick laminated board or ACP board etc. all complete.	Sft.	18.88				
17	P/laying of 15 MM dia G. I. pipe medium class with fittings etc. all complete.	Sft.	90.00				
18	P/laying of 40 MM dia PVC pipe 6K.G./CM square presure etc. all complete.	Sft.	30.00				
19	P/laying of 40 MM dia PVC pipe 6K.G./CM square presure etc. all complete.	Sft.	88.00				

20	P/fitting of 40 MM dia PVC bend etc. all complete.	Nos.	2.00				
21	P/fitting of 110 MM dia PVC bend etc. all complete.	No.	1.00				
22	P/fitting of 110 MM dia PVC door bend etc. all complete.	No.	1.00				
23	P/fitting of 15 MM dia G. M. gate valve etc. all complete.	No.	1.00				
24	P/fitting of 15 MM dia C.P. bib cock etc. all complete.	Nos.	2.00				
25	P/fitting of 15MM dia angle cock etc. all complete.	No.	1.00				
26	P/fitting of 15MM dia commode speray etc. all complete.	No.	1.00				
27	P/fitting of stainless steel soapcase etc. all complete.	No.	1.00				
28	P/fitting of plastic boarder type mirror etc. all complete.	No.	1.00				
29	P/fitting of 4"*2.5" size PVC floor trap etc. all complete.	No.	1.00				
30	P/fitting of towel rod with required rawei plug etc. all complete.	No.	1.00				
31	P/fitting of 16"*22" size p/c/g wash basin with bottle trap, PVC connection pipe, fancy pillar cock,angle cock, bracket, screws etc. all complete.	Set.	1.00				
32	P/fitting of p/c/g commode with commode seat cover and low level plastic flushing cistern, flush pipe,connection pipe, angle cock etc. all complete.	Set.	1.00				
33	P/laying of Non-skid floor tile with 20MM thick under beded mortar in @ 1:4 c/sand mortar and joint filling by white cement or equivelent cement etc.all complete.	Sft.	24.63				

34	P/laying of P/G/C wall tile with 20MM thick under beded mortar in @ 1:4 c/sand mortar and joint filling by white cement or equivelent cement etc.all complete.	Sft.	53.75				
35	Inter connection of water supply pipe line etc. all complete.	No.	1.00				
36	Inter connection of soil pipe line with puntrue of existing chamber etc . all complete.	No.	1.00				
37	P/applying two coat or more coat of exterior weather coat emulsion paint with one coat of cement primer etc. all complete.	Sft.	105.00				
38	P/applying two coat or more coat of plastic emulsion paint with one coat of cement primer etc. all complete.	Sft.	512.22				
39	OTHERS : Rubbish disposalwork, excavated earth disposal, other related on sean work, site clearance etc. all complete.	L. S.	1.00				
				Total:-			
				13% VAT			
				Grand Total:-			