



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको
कोटेशन माग गरिएको सुचना
(सुचना प्रकाशित मिति २०८२/११/११)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Maintenance and Replace of HS Pan sheet at :Old hospital Antenatal ward area. (Only Labor Cost)** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८०/०८१ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा quotation.procurement@bpkihs.edu मा email मार्फत पेश गर्नपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES
DHARAN
COST OF ESTIMATE

NAME OF PROJECT:- H-span color Sheet Roof replace work.(Labour cost only)

PLACE:Old hospital Antinatal ward area.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	fitting of 0.55 mm thick H -Span color sheet or 0.43MM thick color CGI sheet heavy with hilty nut/bolts etc. all complete.(0.55 mm thick H -Span color sheet or 0.43MM thick color CGI sheet Department supply only Labour cost.)	Sft	10,714.54				
2	Dismantling of asbestos cement sheet roof.	Sft	10,714.54				
3	Fitting of 26 gauge medium class color ridge sheet with required nut/bolt with metal and bitumen washer as per instruction. (26 gauge medium class color ridge sheet with required nut/bolt with metal and bitumen washer etc Department supply only Labour cost.)	Sft	198.00				
4	other's : Dismantling asbestos cement sheet dispose site to store section, and site clearance all disposal rubbish materials out side the cap area ,and dismantaling area minar plaster work etc other releted work.repair all cracked wall area by putin and minor touch up by cement primer if required,and dismantal masqtonet jallioutsidethe camp area,minar plaster work, etc other releted work.	Nos	1.00				
				Total:-			
				13% VAT			
				Grand Total:-			