



वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको  
कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०१/१४)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Repair, Maintenance Works At Gynae Office (Bld No 293)** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा [quotation.procurement@bпкиhs.edu](mailto:quotation.procurement@bпкиhs.edu) मा email मार्फत पेश गर्नुपर्नेछ ।

## B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

### COST OF ESTIMATE

NAME OF PROJECT:- Painting & maintenance work.

PLACE:Gynae office room.(Building no -293)

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	p/applying two or more coat of distemper paint over a coat of cement primer.	sft	4,263.80				
2	p/applying two or more coat of weather proof or equivalent exterior emulsion paint over a coat of cement primer.	sft	1,044.36				
3	p/applying two or more coat of enamel paint over a coat of wood primer.	sft	1,324.87				
4	p/applying two or more coat of enamel paint .	sft	997.70				
5	P/fitting of 6 MM thick commercial plywood in false ceiling with 1"*0.5" size she sum bead with required nails/screws etc. all complete.	sft	1,275.55				
6	p/fitting 50*25mm size Sal wood masqtonet jalli fram with stainless steel masqtonet jalli and 4mm thick com. Ply in back saport and saport gudka required nails, screw ,including two ormore coat of enamel paint over acoat of wood primer.	sft	174.65				
7	p/fitting of 4"*3" size salwood door chaukhat with hold fast and required nails,screw etc all complete.	cft	1.32				
8	Dismantling of asbestos cement sheet roof.	sft	2,436.00				
9	fitting of 0.55 mm thick H -Span color sheet or 0.42MM thick color CGI sheet heavey with hilty nut/bolts etc. all complete.(Labour cost only)	sft	2,436.00				
10	fitting of 26 gauge medium class color ridge sheet with required nut/bolt with metal and bitumen washer as per instruction.(Labour cost only)	rft	59.00				
11	other's : Dismantling asbestos cement sheet dispose site to store section, and site clearance all disposal rubbish materials out side the cap area ,and dismantaling area minar plaster work etc other releted work.repair all cracked wall area by putin and minor touch up by cement primer if required,and dismantal masqtonet jallioutsidethe camp area,minar plaster work, etc other releted work.	L/S	1.00				
				<b>Total:-</b>			
				13% VAT			
				<b>Grand Total:-</b>			

