



**वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको
कोटेशन माग गरिएको सुचना**

(सुचना प्रकाशित मिति २०८३/०१/१७)

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित **Interior Furniture Works At VC Office (Padpurti Samiti Room)** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फाँटमा दर्ता गर्नुहुन वा quotation.procurement@bпкиhs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

Bill of Quantity

Name of project : Wooden made partition with door and cubical work.

Place : V. C. offic In BPKIHS area.

SN	Work Description	Unit	Quantity	Rate		Amount	Remarks
				In, No	In, words		
1	P/making and fitting of working table with self In cubical area form 16 MM thick water proof plywoodwithforemica with required fittings and fabical glue and requird nail/screw etc. all complete.(In cubical area) (8'8.5"*2'8"= 23.215Sft.)	Set.	1.00				
2	P/making and fitting of Fixing type cupboard in cubical area form 16 MM thick water proof plywood with foremica with required fittings and fabical glue and requird nail/screw etc. all complete.(In cubical area) (6'1"*2'8"= 16.217+7'2"*2'8"=19.104) = 35.321Sft.)	Set.	1.00				
3	P/making and fitting of plywood partition in cubical area form 12 MM thick waterwith foremica with 16MM thick water proof plywood in frame area in @1'6"C/C in horz. And proof plywood with required fabical glue and requird nail/screw etc. all complete.(In cubical area) (4'0"*6'0"= 24.0-3'2"*1'6"=4.749+2'2.5"*7'5"=16.836) = 36.087Sft.)	Set.	1.00				
4	P/making and fitting of plywood partition for room form 12 MM thick water proof plywood withforemica with 16MM thick water proof ply wood in frame area in @1'6"C/C in horz. And vert. area with required fabical glue and requird nail/screw etc. all complete.(For create of room) (8'10"*10'9"= 94.954+15'10"*9'2.5"+10'9"/2=157.997-2'11.5"*6'9"=-19.966-1'2"*0'6"=-0.583) = 232.402Sft.)	Set.	1.00				
5	P/making and fitting of ply door in partition area form 12MM + 16 MM thick water proof plywood with foremicawith required fittings and fabical glue and requird nail/screw etc. all complete.(In plywood partition area) (2'11.5"*6'9"= 19.966Sft.)	Set.	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				