वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०३/०१

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair, Maintenance and Painting Works At CCTV Room of Security Office*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

Name of Project : Repair and maintenance work for C. C. T. V. monitor room.

Place : In security office block.(Building No.-262).

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remarks
1	Removel of damaged plywood false ceiling and A. C. sheet roofing etc. all complete.	Sft.	429.57				
2	Removel of damaged door shutter etc. all complete.	No.	1.00				
3	P/laying of 12.5MM thick cement plaster in @1:4 cement sand mortar in exact line and level etc. all complete.	Sft.	16.50				
4	P/laying of 3MM thick wall putty in exact line and level etc. all complete.	Sft.	361.42				
5	Fitting of old A. C. sheet with existing j-kook,nut/bolts with new betuimen washer etc. all complete.	Sft.	180.00				
6	P/laying of 6MM thick commercial plywood false ceiling with required bead etc. all complete.	Sft.	249.57				
7	P/fitting of 4MM thick plain clear glass with required nails and beads etc. all complete.	Sft.	2.13				
8	P/fitting of 32MM thick water proff door shuter and aluminium sheet with 3 of of 4" size kabja, 2 no of 6"alu. Cheskini, 2 no of 6" alu. Handle, 1 no of 8" L- drop with required nails/screws. Etc all complete.	Sft.	15.98				
9	P/fitting of p/g/c 20"size orissa pan with low level plastic flushing cystern , flush pipe, connection pipe, angle cock etc. all complete.	Sft.	1.00				
10	P/applying two coat or more coat of plastic emulsion paint with one coat of cement primer etc. all complete.	Sft.	710.02				
11	P/applying two coat or more coat of enamel paint with one coat of cement primer etc. all complete.	Sft.	983.43				
12	P/applying two coat or more coat of enamel paint with one coat of wood primer etc. all complete.	Sft.	577.25				
13	P/applying two coat or more coat of weather proof emulsion paint with one coat of cement primer etc. all complete.	Sft.	255.31				
14	OTHER : Old painting surface cleaning work, crack filling by putin or cement sand mortar,damaged A. C. sheet and false ceiling disposal other related onsean work,rubbish disposal,site clearance.	L. S.	1.00				
			Total :				
			VAT13% :				
			Grand Total :				