वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०३/०५

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair,Painting and Truss Work at Roof top Room ICU Area*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Painting & CCGI SHEET replace work

PLACE:ICU TOP Slab store room.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	P/applying two or more coat of Plastic emulsion paint over a coat of cement primer.	Sft	1,351.33				
2	p/applying two or more coat of weather proof or equivalent exterior emulsion paint over a coat of cement primer.	Sft	467.32				
3	P/applying two or more coat of enamel paint over a coat of metal primer.	Sft	204.20				
4	P/laying 12mm thick cement sand plaster work in @1:4 c/m.	Sft	111.00				
5	P/laying of 75MM thick cement screeding in @(1:2:4)M15 grade cement concrete and punning with crushed aggregate etc. all complete.	Sft	120.00				
6	P/fitting32 mm thick approved brand water proof flush door shutter with 5" inch hinge ISI brand 3no/shutter ,with nails screw , 6"aluminium handle,6" aluminum cheskiney ,10" G.P sliding handle with nails bolts etc all complete work.	Sft	17.22				
7	Dismaintaling of Rcc/pcc concrete slab.	Cft	1.39				
8	F/ fabrication and installation of 50mm die 3.65mm thick M class black pipe post and 40mm x40mmx2mm squire pipe rafter and purling etc as per design & instruction of site engineer.	**kg**	186.62				
9	Dismantling of asbestos cement sheet roof.	Sft	285.53				
10	p/fitting of 0.42mm thick color CGI sheet with hilt, washer, etc all complete.	Sft	528.75				
11	other's : Dismantling asbestos cement sheet dispose site to store section, and site clearance all disposal rubbish materials out side the cap area ,and site clining the old or rough surface to be painted area miner crack filling, miner touch up etc all complete work.	NO	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				