वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०३/२५

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair, Maintenance and Partition Works at Examination Hall at College of Dental*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ। माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Cement board partition and painting work.

PLACE:Dental collage library hall.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	Playing making, fabrication and installation of 91mm thick cement board partition(8mm thick 2 side)Channel section 75mm*1.5mm with M.Spipe Supports as per spacing 750 mm c/c spacing vertical channel &1000 mm spacing horigental frame including required glass wool fill the gaps of partition with required all nails/screw/tap sealent andother satefy measures as per design & instruction up to the satisfaction client complete work.# Materials shall be as per BOQ spacyfy & dimension -31"0"*10' hight,Measurment for bill will be net length of wallx hight of wall for finishing items,location:-BPKIHS,CODS ,2nd floor,workshall be completed with in 7 days from date of agreement.)	Sft	310.00				
2	Dismantling of brick masonry wall .	Cft	29.16				
3	p/applying two or more coat of Distemper paint over a coat of cement primer.	Sft	1,542.00				
2	p/ fitting UPVC frame window with ventilation and with stenless steel masqutonet jalli UPVC natural anodised 60*60mm size Casement window,sash 78mm*60mm,sliding window sash 55mmx36mm approved NS/ISI profile with 5mm clear glass,rubbar gascate,locking set,handle etc as per design & instruction.	Sft	15.00				
3	other's :siteclirance the all rubish materials and repair all cracked wall area by putin and minor touch up by cement primer if required,and dismaintal masqutonet jalli and dismaintal rubish materials out side the camp area,minar plaster work, etc other releted work.	NO	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				