वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०५/०५

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair, Maintenance and Painting Work at PIA Guest House (Bld No=105)*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ। माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

SUMMERY COST OF ESTIMATE

Name of Project: painting and repair work.

Location : Guest house, Building no.-105 and kitchen block.

SN	Work Description	Unit	Quantity	Rate In No	Rate in Words	Amount	Remarks
1	Removel of damage cement plaster.	Sft.	821.03				
2	Removel of damage ply in eaves area and A/C sheet.	Sft.	1,171.39				
3	Removel of door shutter.	Nos.	1.00				
4	P/applying single coat of cement primer.	Sft.	74.99				
5	P/applying single coat of metal primer.	Sft.	423.30				
6	P/applying single coat of wood primer.	Sft.	119.54				
7	P/applying two or more coat of plastic emulsion paint with one coat of cement primer.	Sft.	9,985.23				
8	P/applying two or more coat of enamel paint.	Sft.	3,751.66				
9	P/applying three or more coat of chapra polish.	Sft.	170.73				
10	P/applying two or more coat of aluminium panit.	Sft.	660.56				
11	P/applying two or more coat of weather proof exterior emulsion weather coat paint.	Sft.	778.07				

12	P/applying two or more coat of weather proof exterior emulsion weather coat paint.	Sft.	106.33				
13	P/applying two or more coat of weather proof exterior emulsion weather coat paint with one coat cement primer.	Sft.	5,503.36				
14	P/applying two or more coat of weather proof exterior emulsion weather coat paint with one coat cement primer.	Sft.	519.92				
15	P/fitting of sal wood choukhat with required nali/ screws and hold fast etc. all complete.	Cft.	1.17				
16	P/fitting of 19MM thick water proof plyboard with required nails/screws and existing hardware should be fitting etc. all complete.	Sft.	32.27				
17	P/fitting of 0.39MM thick colour plain sheet with hilty nut/bolt etc. all complete.	Sft.	266.24				
18	P/laying of 12.5MM thick cement plaster in @1:4 cement sand mortar etc. all complete.	Sft.	916.09				
19	P/laying of PCC in @M15 grade cement concrete etc. all complete.	Cft.	24.07				
20	P/laying of 12MM thick gypsum board false ceiling etc. all complete.	Sft.	58.66				
21	P/laying of first class chimney made brick work in in @ 1:4 cement sand mortar etc. all complete.	Cft.	22.54				
22	P/laying of aluminium sheet with required nail/screws etc. all complete.	Sft.	31.79				
23	P/laying of 0.43MM thick colour CGI sheet with required hilty not/bolts etc. all complete.	Sft.	819.25				
20	OTHERS :- Old painting surface cleaning work, crack filling by puttin or c/s mortar, primer touch-up, A/C frame removel, other related on sean work,rubbish disposal,site clearance.	L. S.	1.00				

	Total : Rs.	
	13% VAT :'Rs.	
	Grand Total : Rs.	