वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(पुनः सुचना प्रकाशित मिति २०८३/०६/१६

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Roofing Works at Oral Pathology lab of College of Dental and Pediatric Ward*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ। माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Roofing work.

PLACE: roofing works BPKIHS Dental college oral pathology & paed. Ward 1

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
	Summery sheet -						
(A)	Dental collage oral pathology lab-						
1	Fabrication and installation of and 40mm x40mm 3mm thick square pipe post and purling and tubular truss etc as per design & instruction of site engineer. Contractor must be submitted working truss Design.	kg	3,174.36				
2	F/ fabrication and installation of 65mm Nominal bor and outside die76.1mm and 3.65mm thick M class black pipe post and 8 mm thick base plate etc as per design & instruction of site engineer.	Kg	821.45				
3	Dismantling of Rcc concrete slab .	Cft	36.00				
4	p/laying of pcc for RCC WORK IN@20M grade @1:2:4 cement concrete work with crushed aggregate all complete .	Cft	48.50				
5	Fitting of 0.55 mm thick H -Span color sheet or 0.42MM thick color CGI sheet heavy with hilty nut/bolts etc. all complete.(Labor cost only)	Sft	5,439.84				
6	Fitting of 26 gauge medium class color ridge sheet with required nut/bolt with metal and bitumen washer as per instruction.(Labor cost only)	Rft	121.00				
7	p/applying two or more coat of enamel paint over a coat of metal primer.	Sft	1,346.40				
8	Other's :Site clearance all disposal rubbish materials out side the camp area etc others related work.	No	1.00				
(B)	**Pediatric ward-1**						
1	Fitting of 0.55 mm thick H -Span color sheet with hilty nut/bolts etc. all complete.(Labour cost only)	Sft	7,706.58				
2	Dismantling of asbestos cement sheet roof.	Sft	7,706.58				
3	Fitting of 26 gauge medium class color ridge sheet with required nut/bolt with metal and bitumen washer as per instruction.(Labour cost only)	Rft	138.00				
4	P/laying 12.5mm thick cement sand plaster work in @1:4 c/m.	Sft	257.08				

5	Other's : Dismantling asbestos cement sheet dispose site to store section, and site clearance all disposal rubbish materials out side the cap area ,and dismaintaling area minar plaster work etc other releted work.	No	1.00				
				Total:-			
				13% VAT			
				Grand Total:-			