वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०७१०

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Tile Work At PIA Guest House (BLD NO 105)*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

Name of Project : Floor tile laying work.

Location : PIA Guest house (Bldg. No.-105) area.

SN	Work Description	Unit	Quantity	Rate in No	Rate in Words	Total	Remarks
1	P/laying of Non-skid floor tile with 20MM thick under beded mortar in @ 1:4 c/sand mortar and joint filling by white cement or equivelent cement etc.all complete. (Note : (1) The rate includes dismentalling of existing floor and p/l of required concrete base and design, line and level as per instruction and satisfaction of site incharge (2) Sample of tiles 24"*48" or equivelent standered quality must be approved prior to start the work)	Sft.	2,049.39				
2	OTHERS : Rubbish disposal, other related on sean work,site clearance.	L.S.	1.00				
			Total : Rs.				
			13% VAT : Rs.				
			Grand Total : Rs.				