वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(सुचना प्रकाशित मिति २०८३/०७१०

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair, Maintenance Work At Old AC Plant Room*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Renovation work.

PLACE:Old A/C plant building.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	Playing making, fabrication and installation of 91mm thick cement board partition(8mm thick 2 side)Channel section 75mm*1.5mm with M.Spipe Supports as per spacing 750 mm c/c spacing vertical channel &1000 mm spacing horigental frame including required glass wool fill the gaps of partition with required all nails/screw/tap sealent andother satefy measures as per design & instruction up to the satisfaction client complete work.# Materials shall be as per BOQ spacyfy & dimension -20'0"*10' 10"hight,Measurment for bill will be net length of wallx hight of wall for finishing items,location:-BPKIHS,old A/C plant building completed work.	Sft	216.66				
2	p/laying of non-skid floor tile with 20mm thick under beded mortar in@1:4 c/mortar and joint filling by white cement or equivelent cement etc.all complate work.(Note:(1)The rate includes dismentalling of existing floor and p/l of required concrete base and design, line and level as per instruction and satistaction of site incharge(2)Sample of tiles 24"*48" or equivelent standered quality must be approved prior to start the work)	Sft	266.00				
3	p/laying pcc work in@1:2:4 cement concrete with crushed aggregate etc all complate.	Cft	19.50				
4	p/applying two or more coat of plastic emulsion paint over a coat of cement primer.	Sft	812.43				

5	p/applying two or more coat of weather coat apex altima or all gurad or equivelent paint with over a coat of cement primer.	Sft	117.00				
6	p/applying two or more coat of enamel paint over a coat of wood primer.	Sft	241.76				
7	P/fitting of 6MM thick comercial plywood with required nails/screw etc. all complete.	Sft	148.49				
8	P/fitting of 32MM thick water proof doble pannal false door shuter with 3no, 5" size ISI kabja,2 on of 6"alu. chiskini, 2 no of 6"alu. Handle, 1 no of 8" L-drop required nails/screwsetc. all complete.	Sft	46.00				
9	P/Fabrication and installation of 40*40*2.8mm square pipe post and 40mm x40mm 2.8mm thick square pipe purling,tubalar truss etc as per design & instruction of site engineer.	KG	349.26				
10	Fitting of H-Span color CCGI Sheet with hilt washer etc all complete.(Labour cost only)	Sft	486.66				
11	Fitting of 26 guage medium class colour ridge sheet with requeired nut/bolt with metal and bitumen washer as per instruction.(Labour cost only)	Rft	24.33				
12	Dismaintaling of Rcc concrete slab .	Cft	3.00				
13	p/applying two or more coat of enamel paint over a coat of metal primer.	Sft	160.33				
14	Other's :Site clearance all disposal rubbish materials out side the camp area etc others related work.	no	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				