वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(पुनः सुचना प्रकाशित मिति २०८३/०७/१२

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Repair, Maintenance and Painting Works at CODS-Oral Histo Pathology*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Aluminum partition work.

PLACE:Dental collage histopathology lab area.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate In Words	Amount	Remark
1	P/fitting aluminum frame fixed partition with out door alu.natural anodized 101mm*45mm*1.5mm with 5mm clear glass or acp board including screw ,rubber gasket ,clip etc all complete.	Sft	58.936				
2	P/fitting aluminium frame one way openable casment door with alu.natural anodized 101.6mm*45mm*1.5mm with 5mm clear glass or acp board including screw ,rubbar gascate ,and neccessary new hard ware fitting etc all complate.	Sft	21.0				
3	p/laying first class chimney made brick work in@1:4c/m.	Cft	16.016				
4	p/laying 12.5mm thick cement sand plaster work in @1:4 c/m.	Sft	66.0				
5	p/laying Rcc/ pcc work in@1:2:4 cement concrete with crushed aggregate etc all complate.	Cft	7.5				
6	p/laying & placing rainforcement cutting bending binding etc all complate.	Kg	25.38				
7	p/fitting ordinari form work satring with dismaintaling etc all complate.	Sft	34.25				
8	p/laying of glazed ceramic wall tile approved brand20mm thick under beded mortar in@1:4 with joint filling etc all complate work.	Sft	37.0				
9	p/laying 20mm thick colour marbal with @1:2 cement mortar including grending ,polishing etc all complate work.	Sft	44.786				
10	p/applying two or more coat of distemper paint over acoat of cement primer.	Sft	66.0				
11	other's : site clirance all disposal rubbish material out side the camp area, * brick ,sand,transportation of dental porch to site area etc other releted work.	NO	1.0				
			Total:-				
			13% VAT				
			Grand Total:-				