वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(पुनः सुचना प्रकाशित मिति २०८३/०७/१३

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Cup Boards At GI Surgery and Aluminum Partition Works at Pathology PG Room*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ। माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- Aluminum partition & UPVC Cupboard shutter work.

PLACE:GI.Surjary opd & pathology department PG. Room area.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
	New GI Surgery endoscopy room.						
1	P/fitting of UPVC casement cup board Door with shutter 100*60mm white colour with top and bottom UPVC panel 4" cheskiney ,6"handle, 3"hing ,nails ,screw etc all complate work .	Sft	16.80				
	Collage block pathology department.						
2	P/fitting aluminum frame fixed partition with out door alu.natural anodized 101mm*45mm*1.5mm with 5mm clear glass or acp board including screw ,rubber gasket ,clip etc all complete.	Sft	360.85				
3	P/fitting aluminium frame one way openable casment door with alu.natural anodized 101.6mm*45mm*1.5mm with 5mm clear glass or acp board including screw ,rubbar gascate ,and neccessary new hard ware fitting etc all complate.	Sft	84.00				
4	p/ fitting aluminium frame sliding window with out ventilation and with stenless steel masqutonet jalli aluminium natural anodised 101*38*1.3mm size with 5mm clear glass ,rubbar gascate,locking set,handle etc as per design & instruction.	Sft	48.00				
			Total:-				
			13% VAT				
			Grand Total:-				