वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(पुनः सुचना प्रकाशित मिति २०८३/०७/१३

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Shed Extension Works at Gynae Block*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:- CCGI Sheet shed and fencing work.

PLACE:Gynae emergency visitor wetting shed work.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate in Words	Amount	Remark
1	F/ febrication and installation of 50mm dia 3.65mm thick M class black pipe post and 40mm dia 3.25mm thick M class black pipe raifter and purline etc as per design & instruction of site ingineer.	Kg	210.20				
2	Fitting of 0.42mmthick colour CGIsheet with hilti washer etc all complate.(CCGI Sheet ,hilty, metal washer,bitumin washer, etc Supply by institute.)	Sft	204.00				
3	Earth work excavation in gravel mixed soil shed post foundation.	Cft	29.25				
4	p/laying pccwork in@1:2:4 cement concrete with crushed aggregate etc all complate.	Cft	35.91				
5	P/fitting of 2" opening 10 SWG wire fence heavy coating with binding wire and fitting of boarder (string) wire etc. all complete.	Sft	787.50				
6	p/fitting & laying 10 SWG wire (medium coated)fore boarder wire with binding wire etc all complate .	Rft	425.00				
7	F/ fabrication and installation of 25 mmx25mmx2mm thick squire pipe Metal gate frame and 25 mmx25mmx2 mm thick squire pipe internal Vertical member with 3mm M.S plate and metal sliding handle, metal cheskiney 10",and metal hing ,etc as per design& instruction of site ingineer.(gate size -3'0"*6'8"=2.0no)	Kg	68.29				
8	p/applying two or more coat of enamel paint over a coat of metal primer.	Sft	119.98				
9	other's: siteclirance all disposal rubbish material out side the camp area etc other releted work.	No	1.00				
			Total:-				
			13% VAT				
			Grand Total:-				