वी.पी. कोइराला स्वास्थ्य बिज्ञान प्रतिष्ठान, धरानको

कोटेशन माग गरिएको सुचना

(पुनः सुचना प्रकाशित मिति २०८३/०७/१३

यस प्रतिष्ठानलाई आवश्यक तपशिलका उल्लेखित ***Leakage and Terrace Slab Works at New Academic*** कोटेशनको माध्यमबाट खरिद गर्नुपर्ने भएकोले इजाजत प्राप्त प्रतिष्ठानमा सुचिकृत फर्म, संस्था, कम्पनीबाट अद्यावधिक फर्म दर्ता प्रमाणपत्र, मु.अ.कर दर्ता प्रमाणपत्र, आ.व.२०८१/०८२ को कर चुक्ताको प्रमाणपत्र प्रतिहरु संलग्न गरी यो सुचना प्रकाशित मितिले ७ दिन भित्र कोटेशन पेश गर्नुहुन सुचित गरिन्छ । माग गरिएको कोटेशन तोकिएको म्यादभित्र प्रतिष्ठानको दर्ता चलानी फांटमा दर्ता गर्नुहुन वा quotation.procurement @bpkihs.edu मा email मार्फत पेश गर्नुपर्नेछ ।

B.P.KOIRALA INSTITUTE OF HEALTH SCIENCES

DHARAN

COST OF ESTIMATE

NAME OF PROJECT:-Terrace area Floor Screening work.

PLACE:New academic block top slab area.

S. N.	Work Description	Unit	Quantity	Rate in No	Rate Words	Total	Remark
1	Water proofing coating work- proving and laying of water proofing chemical coating work over well cleaned and brushed roofing surface with sealing of joints with crack seal securing for leakage control works as per instruction complete work.(Leakage check made be done)	Sft	1,140.00				
2	cement screening work- P/laying of aver 50 mm thick cement screening work @1:2:4 cement concrete 1 park cement,2 parks sand and 4 parts 6-10 mm machine crushed washed aggregate including plaster punning and paneling 2.0'x2.0' threading with slope of minimum 1% as per design , drawing and instruction.	Sft	1,140.00				
3	other's :site clerance the all dismantling rubbish materials out side the camp area,and existing slab chipping etc other related work,p/l of c.p100 mm/metal jalli as per instruction,Removal shifting of existing water tank and re-laying the same as per in privious paints touch up work on ceiling and wall of toilet wall /floor tile cleaning etc all complate work.	No	1.00				
			Total=				
			13% VAT=				
			Grand Total=				